

Overcoming the Challenges of Large Capital Programs/Projects

Applying Lessons Learned from Extended Power Upgrades

Smart. Focused. Done Right.®

Introduction

- Effective capital program/project delivery is a critical competency for any electric utility to achieve high performance
- However, project scope creep, schedule delays, and cost increases have become the rule rather than the exception
- Over the past 10 years, the electric utility industry has seen large demands on its projects and construction management organizations to ensure compliance with a number of concerns, including:
 - Plant retrofits and conversions
 - Ash pond closures
 - Fukushima modifications
 - Security upgrade requirements
 - Extended power uprates (EPUs)
- Large capital programs/projects come with a variety of complicated planning, implementation, and workforce/vendor management challenges
- Using EPU projects as an example, we will provide you with ways to overcome these challenges for any large capital program/project

Lessons learned from extended power uprates can be applied to any large capital program/project.

Overview of Power Upgrades

- Power upgrades allow utilities to generate more electricity from their existing nuclear plants
- Since the 1970s, the NRC has approved 154 upgrades, which have collectively added generating capacity equivalent to about seven new reactors
- Three types of upgrades are available to a nuclear plant operator: measurement uncertainty recapture, stretch, and extended

Power Upgrade Type	Increase to Licensed Power Levels	Plant and System Impacts
Measurement uncertainty recapture	< 2%	Implementing improved techniques for calculating reactor power, e.g., utilizing state-of-the-art devices to more precisely measure feedwater flow
Stretch	2 to 7%	Changing instrumentation settings without major plant modifications
Extended	7 to 20%	Significantly modifying to major pieces of non-nuclear equipment, e.g., high-pressure turbines, condensate pumps and motors, main generators, and transformers

Source: www.nrc.gov, Background on Power Upgrades for Nuclear Plants

- As shown in the table above, implementing EUs presents the biggest project challenges, given the need to significantly modify major pieces of plant equipment

EPU Project Challenges

EPU projects pose significant scope, implementation, and workforce management challenges

■ Scope

- Scope is fluid as the EPU project is implemented
- Outages are typically much bigger in scope than a refueling outage, requiring the significant change-outs or upgrades of major equipment
- Changes to the plant configuration (structures, equipment, and systems) must be precisely documented

■ Implementation

- In many cases, the work is done while other units are still in operation
- A high degree of project control rigor is required to accurately track cost and schedule against evolving scope
- Physical security, ALARA limits, lock-out/tag-out requirements, etc., make the work environment very complex

■ Workforce management

- A large number of skilled teams (craft workers and supervisors) that may have never worked together are involved
- Some trades and/or skills are likely to be in short supply
- Many workers are new to a nuclear plant work environment and lack knowledge of nuclear safety and quality standards

Sources:

1. IAEA Nuclear Energy Series No. NP-T-3.9, Power Uprate in Nuclear Power Plants: Guidelines and Experience, 2011
2. Von Lazar, Laszlo, "Lessons Learned from Successful Nuclear Uprate Projects", Nuclear Power International Magazine, Volume 6, No. 4, July/August 2013



Lessons Learned from Recent EPU Efforts

- Planning for contingences is critical. In some cases:
 - Actual costs more than doubled over initially planned costs
 - Outage durations were as much as 25% longer than planned
 - Additional outages were required to complete the work
- Costs and schedules should include contingencies for productivity issues, replacing vs. repairing components, and licensing delays
 - Preliminary cost estimates, based on conceptual scope, may not capture all of the work necessary to complete the project
 - Some components that are initially expected to be repaired or recertified will require replacement, i.e., during configuration control verification, perform a detailed drawing walk-down of pumps, motors, valve controls, etc., to minimize scope surprises
 - Major construction activities at an operating nuclear plant, many of which occur in remote and radiologic-controlled portions of the plant, can cause significant implementation difficulties and delays
 - Space for installation can be extremely tight and may require removal or working around hundreds of interferences
 - Productivity can be slowed due to the specialized and time-consuming procedures to ensure worker safety in radiologic-controlled and electrically sensitive areas of the plant
 - Increasingly conservative regulatory requirements outside of a company's control can cause significant licensing delays
- Obtaining and retaining experienced workers is a challenge
- Active management of vendors is required to ensure productivity is maintained, issues are raised, and progress is on schedule

EPU Project Keys to Success

Work Environment

- Encourage workforce collaboration and the ability of employees to voice concerns early and often to avoid costly errors, re-work, and safety hazards, i.e., maintain a focus on quality and safety
- Develop a self-critical culture focused on improvement and efficiency
- Recognize that the EPU team can not anticipate all the changes that will occur during the project
- Utilize project management technology where possible to improve efficiency and communication
- Hold regular project team meetings and invite senior leadership periodically to reinforce the priority of the project

Planning

- Be honest and realistic about the complexity and uniqueness of the EPU project; investing early in planning and current state analysis can save a lot of rework
- Recognize that the planning process continues all the way to project completion and that the EPU team should always be looking to improve costs, schedule, and general efficiency
- Make benchmarking trips and incorporate lessons learned and insights, e.g., NEDO-33159, from recent EPU and stretch uprates projects into planning
- Bring in field engineers and/or craft supervisors early in the process for review and comment on actual configuration vs. drawings and equipment installation implications
- Hold combined design reviews with members from different disciplines; utilize the experience and expertise from each discipline to come up with a collectively better solution
- Develop integrated work packages to improve efficiency and overall performance

Sources:

1. IAEA Nuclear Energy Series No. NP-T-3.9, Power Uprate in Nuclear Power Plants: Guidelines and Experience, 2011
2. Von Lazar, Laszlo, "Lessons Learned from Successful Nuclear Uprate Projects," Nuclear Power International Magazine, Volume 6, No. 4, July/August 2013



EPU Project Keys to Success (Cont'd)

Implementation

- Manage like a large-scale engineering, procurement, and construction project and not like a modifications project or refueling outage, e.g., funding is stage-gated
- Collect accurate data and monitor relevant performance metrics throughout the EPU project
- Conduct periodic independent project audits using industry experts with previous EPU experience
- Involve employees who will operate the plant during implementation
- Ensure operating staff are adequately trained on how the plant will operate after the power uprate, e.g., operations, maintenance, engineering, radiation protection personnel, etc.
- Update all affected documentation, e.g., operating and maintenance procedures, to reflect the new operating conditions
- Focus on procedure development, training, and simulator modeling to help verify actual plant response vs. expected plant response in power uprated conditions


Vendor/ Contractor Alignment

- Align vendors and contractors with project objectives and the uniqueness of the project
- Ensure vendors and contractors are aware of and held to the tenets of nuclear safety and align their nuclear safety culture with that of your company
- Work collaboratively with contractors and combine cost, schedule, and human performance monitoring tools and processes
- Ensure contracts have clear terms and conditions and are very specific in scope and timing
- Plan for vendor handoffs of work products and resolve disputes promptly to reduce idle vendor time


Sources:

1. IAEA Nuclear Energy Series No. NP-T-3.9, Power Uprate in Nuclear Power Plants: Guidelines and Experience, 2011
2. Von Lazar, Laszlo, "Lessons Learned from Successful Nuclear Uprate Projects," Nuclear Power International Magazine, Volume 6, No. 4, July/August 2013


How ScottMadden Can Help




Capital Program Assessment Overview




ScottMadden's Capital Program Assessment examines how the capital program is implemented—from top to bottom—with a look at the PMO and a review of the performance reporting and tools in place.




Step 6: Recommendations and Action Plan



ScottMadden's approach analyzes these critical areas to provide a detailed assessment of your capital program with actionable recommendations.



Capital Program/Project Management Overview



Focus On

- Organization and governance
- Functional relationship management
- Partnership with other entities

Tools

- Performance Dashboard
- Issue List (high impact and level)
- Monthly Progress Report
- Risk Analysis and Mitigation Plan (high impact and level)

- Inter-project coordination
- Inter-project resource coordination
- Cross functionalities
- Best practice usage
- Documentation management

- Projects List
- Project Procedures
- Project Dashboard
- Milestones Tracking
- Issue List (Aggregated)
- Risk Analysis and Mitigation Plan (Aggregated)
- Weekly and Monthly Progress Reports

- Project milestones
- Costs
- Times
- Business/technical goals

- Project Plan
- Project Documentation Management
- Milestones Tracking
- Risk Analysis and Mitigation Plan
- Change Request Management
- Issue List Management
- Project Baseline and Progress Report
- Weekly Progress Meeting Minutes
- Weekly Progress Report
- Monthly Progress Report

```

graph TD
    A[Scott/Madden Capital Program/Project Assistance] --- B1([ ])
    A --- B2([ ])
    A --- B3([Capital Program/Project Tools and Performance Reporting])
  
```

F.G.P.						PROJECTS DRIVING BOARD										
						Status	Tendency (previous)	Tendency (actual)	TIME			COST (Euro)			Open Issues	
Order	Project	Description	Project Manager	Type	Impact	30-Apr-01	31-May-01		Baseline Start	Baseline End	Forecast End	Budget	Actual	Forecast	& Critical Point	
CMPR0027	RGCT0090	Powetrain Retrofit	Sorrell	F	M				1-Jan-00	31-Aug-00	31-Aug-00	26,550	26,085	26,550		
CMV00007	RGCT1572	Ingr. Vernein Plant	Seaford	F	M				15-Jan-01	28-Sep-00	28-Sep-00	82,633	0	82,633		
CMPR0015	RGCT2982	HMS new devel.	Riley	F	H				1-Jan-01	31-Dec-01	31-Dec-01	108,785	0	108,785		
CMPR0016	RGCT3004	Web professional	Riley	F	M				15-Apr-01	31-Oct-01	31-Oct-01	71,975	0	71,975		
CMPR0038	RGCT1071	Gatesia D.Cent	O'Leary	O	L				7-Mar-01	30-Jun-01	30-Jun-01	23,780	0	23,780		
CMPR0018	RGCT3047	US. WRFQ	Briggs	F	L				1-Mar-01	31-Jul-01	31-Jul-01	77,488	0	77,488		
CMPR0025	RGCT0014	Engine Sports Air.	Breigot	O	M				12-Apr-01	31-Oct-01	31-Oct-01	158,479	0	158,479		
												Total	549,040	26,085	549,040	
Legend																
Type	Compulsory (O)				Impact	High (H)			Tendency		Flat					
	Perm (P)					Low (L)					Rising					
	Opportunity (S)										Falling					

The chart displays the relationship between Value (Y-axis) and Manageability (X-axis) for various project management components. The components are represented by colored bubbles, and lines connect them to show relationships.

Legend:

- Data Migration and Go-Live (Blue)
- Resources (Yellow)
- Change Management (Teal)
- Project Governance (Red)
- Project Management (Orange)
- Technological Architecture (Brown)
- Application (Dark Red)
- Legacy Systems (Light Blue)
- Interfaces (Dark Blue)
- Project Documentation (Light Teal)

Key Relationships (Lines):

- Data Migration and Go-Live is connected to Project Governance, Change Management, and Interfaces.
- Project Governance is connected to Change Management and Interfaces.
- Change Management is connected to Interfaces.
- Interfaces is connected to Technological Architecture, Project Documentation, and Application.
- Technological Architecture is connected to Project Documentation.
- Project Documentation is connected to Application.
- Resources is connected to Project Management.
- Project Management is connected to Legacy Systems and Application.
- Legacy Systems is connected to Application.
- Application is connected to Legacy Systems and Project Governance.

The screenshot displays a complex project management dashboard with multiple sections:

- Top Navigation:** Includes fields for CODE, NAME, and TYPE.
- Project Overview:** A table with columns for CODE, NAME, TYPE, and a Date field set to 05/17/2003. Below this is a table with columns for ORDER, PROJECT, Prio Item, Implementation, Compulsory, Item, and Opportunity.
- Descriptions:** A section for "Over Legal Entity Functions" and "Over Legal Entity Functions".
- Impact on other Projects/Applications:** A section with a "Name" field.
- Operating Costs Summary:** A table with columns for Description, Amount, and Unit. It shows a total of 100000.00.
- Issues:** A section with a table for Open Issues, Closed Issues, Total Issues, and S/Open Issues/Total Issues.
- Project Characteristics:** A section with a table for Project Characteristics.
- Best Practice Adherence:** A section with a table for Best Practice Adherence.
- Overall Project Status:** A section with a table for Overall Project Status.
- Impact:** A section with a table for Impact.

PROJECT PRGnnnn Implementation		MONTHLY STATUS REPORT	
REF.	1 / 24		
MONTH	MARZO 2001		
PHASE	PROTOTIPAZIONE		
PROJECT STATUS			
F' stato definito il System Integrator. F' stato definito il Piano di progetto. F' stata impostata la proposta di Struttura Organizzativa di Progetto. F' stata impostata la baseline per i costi di Progetto Sono state attivate le Procedure di Gestione Scope Change Request, di Gestione Issue List e di Gestione della Documentazione. F' stato Definito il tool di gestione della documentazione di Progetto. F' stata impostata l'Analisi del Rischio.			
OPIN ISSUES		ACTIONS	RESPONSIBLE
1 - L'Ambiente di Prototipazione non è disponibile.		Predisporre ambiente prototipazione	IT Project Manager
			DUE DATE
			06/04/01
NEXT STEPS			
Ottimizzazione Struttura Organizzativa di progetto. Definizione dei componenti del team da parte del Responsabile/Referenti. Verifica profilo di spesa e budget Architettura Tecnologica. Impostazione attività di Quality Assurance.			
APPROVED CHANGE REQUESTS			
Nr.	Description	Approval Date	Allocated Contingency

The chart displays three data series over time from January 2001 to February 2003. The 'Actual' data is only available for the first two months. The 'Baseline (Core)' and 'Baseline (Contingency)' series provide forward-looking estimates, with the contingency baseline generally higher than the core baseline.

Month	Actual	Baseline (Core)	Baseline (Contingency)
Jan 01	0	0	0
Feb 01	15020	15000	15000
Mar 01			
Apr 01			
May 01			
Jun 01		19208	19108
Jul 01			
Aug 01		21366	21531
Sep 01			
Oct 01		25355	25330
Nov 01			
Dec 01		28733	29058
Jan 02			
Feb 02		33000	33375
Mar 02			
Apr 02		34903	34678
May 02			
Jun 02		36920	36945
Jul 02			
Aug 02		38489	38489
Sep 02			
Oct 02		38100	40949
Nov 02			
Dec 02			
Jan 03			
Feb 03			

ORDER PROJECT	COMM PRG-Tmn	Name/Comm Implementation	BASELINE VS ACTUAL VS FORECAST			E.G.P.
			COST (Euro)			
Cost Type	Cost Element		Baseline	Actual	Forecast	Notes
System Development	Development & Implementation		18,550	2,434	18,550	
	External Resources		0	0	0	
	Operational/Applicational Mgmt		3,783	3,783	3,783	
	Total System Development		22,333	6,217	22,333	
Legacy Management	HW/SW Design & Consultancy		1,572	1,572	1,572	
	HW/SW Acquisition		6,500	6,500	6,500	rendi relativi all'architettura tecnologica saranno dettagliati al termine
	SW Licences		3,145	3,145	3,145	dalla lista di definizione dei requisiti)
	Total HW/SW Mgmt		11,217	11,217	11,217	
	Total External Costs		33,550	17,434	33,550	
	Total Internal Resources		4,564	1,674	4,564	
	Partial Project Total		38,314	19,108	38,314	
	Contingency		2,835	100	375	Importo da attivare 5 Steps Change Request
	Overall Project Total		40,948	19,708	38,489	

Figure 1 is a Gantt chart illustrating the timeline of the study from July 2014 to July 2015. The chart tracks the duration of various activities:

- Preparation of the study:** Yellow bars, spanning from July 2014 to approximately August 2014.
- Data collection:** Orange bars, spanning from approximately August 2014 to September 2014.
- Data analysis:** Green bars, spanning from approximately September 2014 to November 2014.
- Writing the thesis:** Blue bars, spanning from approximately November 2014 to February 2015.
- Final review:** Green bars, spanning from approximately February 2015 to July 2015.